



## SNCR Experience on Large Coal-Fired Boilers with Difficult Operating Conditions

*Kelly Borgen, Engineer, Jeffrey Energy Center*



# JEFFREY ENERGY CENTER

ST. MARYS, KANSAS

- Three (3) eight-corner, tangentially-fired units designed for PRB coal
  - Units 1, 2, and 3 commissioned in 1978, 1980, & 1983, respectively
  - CE subcritical drum boilers – 5,050,000 lb/hr capacity
  - 800 MWg nameplate
- Dispatched as part of the Southwest Power Pool (SPP)




## PROJECT OVERVIEW

---

- 2010 Consent Decree required JEC NOx emissions upgrades
  - Coordinated effort with the Environmental Protection Agency (EPA) and the State of Kansas
    - SCR required to be installed on one unit at a minimum – selected Unit 1
    - Option to build a second SCR or comply with a 0.10 lb/mmbtu site-wide NOx limit
  - Stacked technologies to achieve site-wide NOx limit without an additional SCR
    - Neural network combustion and sootblowing optimizers on all three units
    - Boiler modifications on Units 2 & 3
      - Additional elevation of over-fire air (tertiary over-fire air, TOFAs)
      - New low-NOx burners with horizontally biased combustion
    - SNCRs on Units 2 & 3


# PERFORMANCE OBJECTIVES & SCHEDULE

- Control NOx emissions over large load range (39-100% MCR)
  - Reduce NOx from ~0.17 to <0.125 lb/mmbtu with combustion modifications
  - Reduce NOx from 0.125 to <0.115 lb/mmbtu with SNCRs on Units 2 & 3
  - Reduce NOx from 0.17 to 0.04 lb/mmbtu with SCR on Unit 1
- Ammonia slip <10 ppm for SNCRs
- Maintain CO and other unit performance metrics




# DESIGN CHALLENGES

- Limited time
- High FEGT due to high net heat input per plan area and PRB coal
- Challenging SNCR reagent distribution due to large furnace cross-sectional area and superheat pendants in upper furnace
- Boiler combustion modifications completed simultaneously with SNCR install, resulting in:
  - Very low baseline NOx (~0.125 lb/mmbtu)
  - High CO concentration at the point of urea injection (~1600 ppm)
  - Even higher FEGT
  - Need for modeling of both the boiler modifications and the SNCR




# HIGH UPPER FURNACE TEMPERATURE

## FULL LOAD - CFD MODEL




Furnace Centerline Temperature




TOFA and Lower Windbox Elevations


Superheater Platens Elevation 1464'



# DROPLET TRAJECTORIES AND NOX PROFILE INJECTION MODELING




Full Load:  
Wall Injectors and Multiple Nozzle  
Lances (MNLs)



65% Load: Wall Injectors Only

# SYSTEM SUMMARY

- Fuel Tech's injection strategy
  - Three (3) zones of wall injectors
  - One (1) zone of MNLs
- Zones 1 and 2 consist of NOxOUT® wall injectors
- Zone 3 consists of HERT™ wall injectors
- Zone 4 consists of multiple nozzle lances (MNLs)



## SOLUTIONIZING SYSTEM

---


- JEC has ability to receive both dry and aqueous urea
- Solutionizing system scope of supply
  - 3,100 ft<sup>3</sup> dry urea silo
  - 10,000 gallon solutionizing tank w/ mixer, heaters, and load cells
  - Solutionizing module with density meter and strainer
  - Dehumidification unit
  - Redundancy in heating and mixing
  - Remote I/O panels controlled by DCS
  - Treated water system
- Significant reagent cost savings with dry urea solutionizing system vs. 50% aqueous urea delivery

## PERFORMANCE TEST RESULTS


Unit	Unit 3		Unit 2	
Load Condition	Full Load	Mid Load	Full Load	Mid Load
NOx after Combustion Mods (lb/mmbtu)	<b>0.125</b>	<b>0.108</b>	<b>0.120</b>	<b>0.104</b>
NOx with SNCR (lb/mmbtu)	<b>0.112</b>	<b>0.101</b>	<b>0.107</b>	<b>0.098</b>
NH3 slip (ppm)	<b>8.8</b>	<b>6.9</b>	<b>7.8</b>	<b>5.8</b>

- Met or exceeded performance objectives
- Overall NOx performance on Unit 2 with SNCR in service is approximately 5%-7% better than Unit 3
  - Benefits include flexibility in compliance with site-wide NOx limit and annual urea cost savings

# JEC 2 AND 3 HOURLY NO<sub>x</sub>



# JEC 2 AND 3 SNCR CHEMICAL FLOW



## BUMPS ALONG THE WAY & LESSONS LEARNED

---

- Short timeline resulted in oversights and rework.
  - Freeze protection
  - Water pretreatment system
  - Air compressors
- Simultaneous install of combustion modifications and SNCR produced challenges in predicting performance and establishing guarantees.
- Coordination among all involved parties was key.
- Learned from Unit 3 and made the most of the opportunity to improve on Unit 2.

## PROJECT SUMMARY

---

- Jeffrey Energy Center is able to comply with the Consent Decree
  - Flexible emission compliance plan
  - Significant capital savings
  - Reduced consumption of urea from lower baseline NOx
  - Operating cost savings from SNCR operating at low loads
- Units control NOx emissions over wide load range offering operating flexibility
- Flexibility with reagent supply options
- SNCRs have been in normal operation since fall 2014
  - NOx remains well controlled



Questions?

